Butler Community College

Request for Proposal Access Controls & Video Surveillance

RFPID: DT-PHYSICALSECURITY-ELD-2018

6th, April – 2018

****

Submitted Questions and Answers

****

Submitted 4/2/18

Question:

Are Life Safety Power supplies and enclosures required, or can alternates be submitted?

Answer:

Life Safety Power Supplies and enclosures are required.

Submitted 4/2/18

Question:

Are access credentials required? What type and quantity? (i.e. Keyfobs or cards)

Answer:

Yes, we will need 5000 iClass cards.

Submitted 4/2/18

Question:

Is a badge printer and photo capture camera required?

Answer:

Badge Printer and photo capture is not apart of this RFP

Submitted 4/2/18

Question:

Are all video and access control servers provided by Butler? Under the scope of work, specifications & requirements section, (5.1 Requirements) it lists (5) locations that will require a small server (DVR) for local storage. Can specifications for those servers be provided to Butler for the college to purchase?

Answer:

The Following locations will need their own server. The server will need to be able to store 30 days of video at 7 frames a second and full resolution. Please provide your storage calculator for each site in the bid.

Fire Science
Rosehill
AG
Service Center
9100 Building

Submitted 4/2/18

Question:

Is integration to Avigilon required from existing DMP and Bosch equipment? Is the existing Bosch equipment to be replaced with DMP panels?

Answer:

All existing panels including Bosh panels will need to be replaced with DMP panels. This will not integrate with Avigilon

Submitted 4/2/18

Question:

Building 2610 has a Best lock on the garage to hallway door. Plans do not show a card reader for this door. Does this location need to have a card reader?

Answer:

The lock on the hallway door to the garage will not be replaced, it will be removed.

Submitted 4/11/18

Question:

On Addendum #1 for physical security, Rose Hill lists 2 additional cameras. No Rose Hill prints were provided at the walk through. Are these prints available for distribution or is a walk through required?

Answer:

At this time there are no blueprints, we were just notified of an addition that will be added to the building. If we are provided blueprints before the deadlines of this rfp, we will send them out.

Submitted 4/11/18

Question:

On Addendum #1 for physical security, building 1500 lists 223 and 222 as getting access control. During walk through door 233 was noted as having existing electrified lockset. Should the addendum list 222 and 233 as the doors needing access control?

Answer:

All existing access controls will be replaced in this project. 222 and 233 will need new access controls on them.

Submitted 4/11/18

Question:

6000 building print included in documentation. No cameras or access control is specified on prints. Were the devices omitted or is the facility not part of this project?

Answer:

 Please omit the 6000 building, they are apart of the master blue prints but not apart of the rfp.

Submitted 4/16/18

Question:

Upon multiple reviews of the provided prints, quantities listed in addendum #1 for card reader/locks and door position switch lines are not equal. Correct quantities for below items requested.

a. Position Switch Doors- listed as 112, while count produces 103.

b. HID Card Readers- HES Locks- Door quantity to 210. Counts of provided prints list 192.

Answer:

 Please reference the correct numbers on the excel document "AccessControlsCount. Total numbers are as follow

AC:190

M:102

VD:12

Submitted 4/16/18

Question:

Building 2000-1 has multiple doors listed as VD. During the walkthrough it was conveyed that these doors will require a strike, door position switch and request to exit motion, but not a card reader

Answer:

Both doors need to have electronic locking sets and be able to unlocked for scheduled events.

Submitted 4/16/18

Question:

Will a double door require two locks or one? This decision will affect both the operation of the door and the cost of the project.

Answer:

Correct, both doors need to have electronic locking sets

Submitted 4/17/18

Question:

Will all access control panels communicate over BCCC network to one server, or will the remote buildings with their own servers need to be licensed for access control as well as video?

Answer:

There will be one Access Control Server for all sites to communicate with.

Submitted 4/17/18

Question:

Are there device counts available for the Rose Hill location? Addendum references additional items however original device count/listing has not been provided.

Answer:

There is no Access Controls in Rosehill. The addendum calls out 2 – 6.0 L-H4F-D01-R cameras.